

17-16-3W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,


Wichita, Kansas

Company. THE ATLANTIC REFINING COMPANY
 Farm. Nelson No. 2

SEC. 17 T. 16 R. 3W
 C W/2 SE NW

Total Depth. 3435
 Comm. 9-13-53 Comp. 9-30-53
 Shot or Treated.
 Contractor. Brack Dilling Co., Inc.
 Issued. 11-14-53

County Saline
 KANSAS



Elevation. 1375 DF

8 5/8" 383' cem. w/200 sx
 4 1/2" OD 3433' cem. w/200 sx

Production. Pmp. 31 bbls. oil &
 38 wtr.

Figures Indicate Bottom of Formations.

surface hole	51
shale & shells	125
shale	150
shale & shells	383
lime	500
lime & shale	900
shale & shells	945
lime & shale	2973
lime	3175
lime & shale	3240
shale & shells	3310
lime & shale	3428
dolomite	3435
Total depth	

Scout Tops:

Brown lime	2204
Lansing	2276
Mississippi	2942
Kinderhook	3201
Maquoketa shale	3394
Maquoketa dolomite	3432

Remarks;

Acidized open hole 3433-3435 with
 250 gals. 15% acid and M-38.
 Sandfraced same interval. On
 October 15, 1953 tested at rate
 of 31.29 BO/24 hrs. from open hole
 3433-3435. (Maquoketa dolomite)