

17-16-3W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- THE ATLANTIC REFINING COMPANY
Farm- Oborg No. 4

SEC. 17 T. 16 R. 3W
C W/2 NE NW

Total Depth. 3425
Comm. 9-2-53 Comp. 9-16-53
Shot or Treated.
Contractor. Brack Drilling Co.
Issued. 11-14-53

County Saline KANSAS



Elevation. 1364 RKB

8 5/8" OD 385' RKB cem. w/1010 sx
4 1/2" OD 3423' cem. w/200 sx

Production. Pmp. 38 bbls. oil
& 29 wtr

Figures indicate Bottom of Formations.

shale & shells	60
sand	95
shale & shells	290
sand	320
shale	350
shale & lime	385
shale & shells	505
lime & shale	1050
shale	1365
shale, lime shells	1665
shale & lime	2455
lime	2600
lime & shale	2670
shale, shells, lime	2770
lime & shale	2975
lime	3160
lime & shale	3390
shale	3422
dolomite	3425
Total depth	

Scout Tops:

Brown lime	2193
Lansing	2265
Mississippi	2924
Kinderhook	3193
Maquoketa shale	3385
Maquoketa dolomite	3422

Completion. Acidized
open hol 3423-3425 dow 4 1/2"
casing w/250 gals. Dowell
M-38 15% acid. Sand oil
treated. Tested 30 BO/10
hrs on 9-29-53 from open
hole 3423-25 (Maquoketa
dolomite.)