

17-16-3W

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
500 East Murdock, Wichita, Kansas

Company-NATIONAL ASSOCIATED PETROLEUM CO.
Farm-Swenson "B" No. 2-B

SEC. 17 T. 16 R. 3W
C SW SW

Total Depth. 3436

Comm. 12-9-52

Comp. 12-19-52


Shot or Treated.

Contractor. Exploration Drilling Co.

Issued. 2-21-53

County Saline

KANSAS



Elevation. 1374

Production. 96 bbls., 2% water

CASING:

10 3/4 set at 163' w/ 150 sx cement
8 5/8 set at 490' w/ 100 sx cement
5 1/2 set at 3433' w/ 75 sx cement

Figures Indicate Bottom of Formations.

surface	185
shale	230
shale & shells	380
anhydrite	385
anhydrite & shale	435
anhydrite	517
shale & shells	610
shale & lime	1275
shale & shells	1600
shale	1900
shale & lime	2050
shale	2300
shale & lime	2370
shale	2439
sand	2470
shale & lime	2950
chert & shale breaks	2991
cherty lime & shale	3038
lime & shale	3090
lime & chert	3137
lime, chert & chat	3165
lime, shale & chert	3207
shale & lime	3436
Total Depth	

SCOUT TOPS:

Lansing	2277
Mississippi lime	2934
Winderhook	3400
Maquoketa shale	3415
Maquoketa dolomite	3432