

19-16-3W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- NATIONAL ASSOCIATED PETROLEUM COMPANY
Farm- Bethany College No. 1

SEC. 19 T. 16 R. 3W
NE NE NW

Total Depth. 3641 RB
Comm. 11-20-51 Comp. 12-5-1951
Shot or Treated.
Contractor. Holm Drlg Co.
Issued. 3-1-52

County Saline
KANSAS



CASING:
8 5/8" 425'

Elevation. 1436
1435 (2nd)
Production. dry

Figures Indicate Bottom of Formations.

shale	145
sand, shale	165
shale, shells	300
anhydrite broken	420
Lost Circulation @ 300	
and dry drilled to	425
anhydrite	425
shale	475
shale, lime	1085
shale, shells	1880
shale, lime	2045
lime	2250
shale, shells	2415
lime, shale	2440
lime	3083
lime cherty	3254
shale, lime & cherty	3281
shale, lime	3370
shale	3553
Cored	3553 to 3557
shale, lime	3624
lime	3641
Total depth	

Top: Scout.	
Heebner	2165
Brown Lime	2325
Lansing	2396
Mississippi	3040
Kinderhook	3323
Maquoketa	3551
Viola	3615

Note: - All above depths are rotary bushing measure. Deduct 5' for ground level on measure.