

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock,

Wichita, Kansas

29-16-3W


Company- DeWEESE-SANDERSON
 Farm- Nordling No. 1

SEC. 29 T. 16 R. 3W
 C W/2 NW SE

Total Depth. 3393'
 Comm. 8-22-59 Comp. 8-31-59
 Shot or Treated.
 Contractor. Melland Drlg. Co.
 Issued. 12-12-59

County Saline

KANSAS



Elevation. 1360' RB

Production. 25 BOPD

CASING:

8 5/8" 356' cem w/341 sx.
 4 1/2" 3390' cem w/50 sx.

Figures indicate Bottom of Formations.

surface soil & clay	40
sand	80
shale, shells & gypsum	356
lime	425
lime & gypsum	535
lime & shale	650
sandy lime	680
lime w/some shale	830
lime & shale	1100
shale & lime shells	1785
lime & shale	2086
shale & lime	2275
lime & shale	2700
shale & lime	2735
lime & shale	2928
Mississippi lime	3165
shale & lime	3190
shale	3393 RTD
Total Depth	
TOPS: SCOUT	
Mississippi	2921
Kinderhook	3151
Maquoketa	3390