


32-16-3W

Company - BAY PETRO. CORP.  
Farm - Holm No. 1

SEC. 32 T. 16 R. 31  
NW NW NW

Total Depth. 3639  
Comm. 6-24-51 Comp. 7-11-51  
Shot or Treated.  
Contractor. Musgrove Petro. Corp.  
Issued. 9-15-51

County. Saline  
KANSAS



CASING:

8 5/8" 365' cem. w/265 sx  
5 1/2" 362 1/2' cem. w/100 sx

Elevation. 1358

Production. 207 BO

Figures Indicate Bottom of Formations.

surface and red bed	100
red bed, shale, sand shells	300
shale	365
sandy lime	515
sandy shale	720
sandy lime	965
shale & lime	1100
shale & shells	1390
shale	1650
shale & lime	1790
lime	1875
shale & lime	1915
sandy lime & shale	2000
shale & shells	2140
lime & shale	2275
lime	2350
lime & shale	2550
lime	2625
lime & shale	2845
shale & shells	2945
shale & chat	3125
chat, lime & shale	3162
lime	3185
shale & lime shells	3235
shale & shells	3290
shale	3338
shale & lime shells	3363
shale & sand	3415
shale & lime	3447
shale, chert & lime	3470
lime	3525
lime & shale	3615
ar buckle	3639 RTD
Total Depth	

Scout Tops:

Lansing	2284
Mississippi	2946
Misener	3363
Maquoketa Shale	3366
Maquoketa Dolomite	3407
Viola	3461
Simpson	3563
Ar buckle	3614