

KANSAS DRILLERS LOG

PI No. 15 — 101 — 20,140
County Number

Operator
Abercrombie Drilling, Inc. & Beren Corporation

Address
801 Union Center, Wichita, Kansas 67202

Well No. 1 Lease Name HUCK

Footage Location
1980 feet from (N) line 1980 feet from (W) line

Principal Contractor
Abercrombie Drilling, Inc.

Geologist
George Dent

Spud Date
March 19, 1975

Total Depth
4530'

P.B.T.D.

Completed
March 27, 1975


Oil Purchaser
None

S. 7 T. 16S R. 30 W

Loc. SE NW

County Lane

640 Acres
N



Elev.: Gr. 2763'

DF 2766' KB 2768'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"		200.39'	Sunset	160	

Surface Clay & Sand
Shale
Shale & Red Bed
Shale & Lime
Lime & Shale
Shale & Lime
Lime & Shale
Lime
Rotary Total Depth

0
140
2600
2995
3115
3430
3555
3840
4530
4530

ELECTRIC LOG TOPS:

Anhydrite 2177
B/Anhydrite 2204
Topeka 3572
Heebner 3805
Toronto 3824
Lansing 3843
B/Kansas City 4202
Fort Scott 4362
Cherokee Shale 4397
Mississippian 4471
ELTD 4532

DST #1 (3812-3840) 30", 45", 90", 60"
Weak Steady Blow throughout test.
Recovered 220' salt water. IFP 16#-35#;
IBHP 1070#; FFP 58#-118#; FBHP 1022#.

Plugged and Abandoned:

1st Plug Set @ 1000' with 70 sx.
2nd Plug Set @ 200' with 20 sx.
3rd Plug Set @ 40' with 10 sx.