

So. Hattenberg Prospect

State Kansas County Ellsworth

Company Messner Leitch & Co. Well No. 1


Farm Schlesinger "C"

Survey _____

Block No. _____ Sec. 31 Twp. 16⁶ Range 10^w

Co-Ord. _____ Elev. 1281 DF
1284 KB

app. 100' No. 7 1/2 hwy 4 rd 4



also ordered 9/16
Conte - Mumford Delg.
25% - A.A. Seeliger, Jr.
25% - L. J. Flynn
6.25% - K.W. Tringer, Jr.
43.75% - ~~Messner Leitch & Co.~~
RLM + LK. Smith
in equal shares

3400' anhydrite test to be
run by 8-20-68

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line 420 Ft. from S. Line _____

660 Ft. from W. Line _____ Ft. from E. Line _____

Date	Depth	
8-20-68		M. J. R. J. - Speed (3:30 P.M.) 8 7/8" @ 300' w/150 qt. cement 3 1/2% gal, 2 1/2% c.c. P.D. @ 9:30 P.M. 8/20/68 (Cement line. by Globe)
8-21		with w.o.l 2:00 P.M. Delg. out from under roof.
8-22	1490	Delg.

654-683 - anhydrite

Date	Depth	
		694954
8-23-68	2100'	Drly.
8-24-68	2683	Drly.
8-25-68	2890	Drly.
8-26-68	3071	Drly.
	D.S.T. #1	2914-2937 Open 50 min.
		shut in 30, Open 60 min.
		shut in 30, Recovered 45' mud
	lin 30"	IBHP 298#; I.F.P. 23# ISIP 1649; IFFP 298 Final FBHP 262; F.F.P. 23 Temp. 105° Flow 23, Final shut in 262
	2824	Queen Hill (-940)
	2909	Heebner (-1025)
	2927	Toronto (-1043)
	3011	Brn. Lmc (-1127)
	3025	Lansing (-1141)
8-26-	DST #2	3016-3071 Op lhr stry blo.
		Rec. 45' Mud IBHP 448-320 #
	lin 30"	IFP 53#-53# good sho, Temp 105°
8-27-	DST #3	3071-3110 Op lhr good blo.
		Rec 30' HV. 0.4m, 60 ocm, 920' 31.
		oily w try mud Temp 105°
	lin 30"	IBHP 836-700# IFFP 63#-FFP 117#
		3130 Drly.
8-28	3260	Drly.
	DST #4	3194-3220 open 1 1/2 hrs

State Kansas County Ellsworth

Company Messman-Rinchart Oil Co. Well No. 1


Farm Schlessiger "C"

Survey _____

Block No. _____ Sec. 31 Twp. 16S Range 10W

Co-Ord. _____ Elev. 1884 KB

App. 100' N of S/2 SW 1/4 NE 1/4



Page 2

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
		shut in 30 min; 90' gas in pipe <small>Bottom hole pipe</small> rec'd 30' O.C.M.; I.S.P. 480#;
		I.F.P. 21; F.F.P. 27; F.S.I.P. 95#;
		temp. 107°
8-29	3328	Conglomerate (-1444)
	3372	Arbuckle (-1488)
		staining & porosity
	3383	R.T.D.
8-30		R.D.A. plugged 8:30 A.M.

694954

Date

Depth

1 #
No. 5.

DST. 3368-3383

8/29/68

Open 7 hr 48". weak blow

RTD 3383

Rec. 20' # HV9 ocm, 100' ocm, 60' mdy.

Sulphur Ntr. in D.Cs.

Air 30" IBHP 49# FBHP. 1064 #

IFP 54 # FFP 101 #

Temp. 107°F

8/30/68

D & A

Plugged 3:30 am