

WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas


1-16-4W

Company - THE ELDORADO REFINING CO.
Farm - Olsson No. 1

SEC. 1 T. 16 R. 4W
NW NW SW

Total Depth. 3428
Comm. 5-12-51 Comp. 5-24-51
Shot or Treated.
Contractor. Sterling Drlg. Co.
Issued. 7-21-51

County. Saline
KANSAS



CASING:

8 5/8" 342' cem. w/225 sx
5 1/2" 3425' cem. w/50 sx

Elevation. 1314 DF

Production. 528 BOPD

Figures Indicate Bottom of Formations.

surface clay & shalo	335
anhydrito	365
limo	1050
limo & shalo	1245
shalo & sholls	1800
limo & shalo	2365
limo	2780
shalo & limo	2885
limo	3030
limo & chort	3160
limo	3191
shalo	3425
limo	3428
Total Depth	

Tops: D.F.	
Miss.	2911
Kinderhook	3204
Hunton	3346
Maquokota Dolomite	3422

DST: 3423-26, op. 30 min.,
strong blow, rec. 540' oil
& 120' O.C.M. SIP 1245 1/2 / 20"

CABLE TOOLS RECORD:

Drilled plug. Cleaned out.
Hole filled 800' of oil in 1
hr. After cleaning and swabbing
well, it filled up 3400' in 8
hrs. Swab test showed well
making 14 bbls. per hr.