

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY  
508 EAST MURDOCK - WICHITA, KANSAS

1-16-4W

COMPANY T. A. PHILLIPS & J. L. SANDERSON

SEC. 1 T. 16 R. 4W  
LOC. NW NW NW

FARM Ryding

NO. 1

COUNTY Saline

TOTAL DEPTH 3443'


COMM. 3-17-51

COMP. 3-31-51

SHOT OR TREATED

CONTRACTOR Sterling Drlg. Co. & Arrow Well Servicing Co.

ISSUED 5-26-51



CASING

13" 153' cem w/200 sxs  
8 5/8" 355' cem w/ 125 sxs  
4 1/2" 3439' cem w/75 sxs



1326 RB (and.)

ELEVATION 1324 DF

PRODUCTION I. P. P. 508 bbls.

FIGURES INDICATE BOTTOM OF FORMATIONS

clay & shale	250
shale	325
anhydrite	370
lime & shale	1780
lime	2085
broken lime	2210
shale	2280
lime	3200
shale	3439
lime	3443
Total depth	

\*Tops:

Burgess sand	2914
Mississippi lime	2916
Kinderhook shale	3200
Misener sand	3338
Hunton	3359
Maquoketa shale	3367
Maquoketa dolomite	3439

\*All measurements are from the top of Rotary Bushing which is 2' above the Derrick Floor

Cemented 8 5/8" casing through 1" with 104 sacks cement, 3 sacks C. C. (1 sack Floseal)

Drill stem test 3440-3443, open 1/2 hr., recovered 1080' gas  
425' oil, 15 min. Bottom hole pressure 1248 lbs.