

1-16-44


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PHILLIPS & SANDERSON
Farm- Riding No. 2

SEC. 1 T. 16 R. 4W
SW SW NW

Total Depth. 3423
Comm. 8-10-51 Comp. 8-22-51
Shot or Treated.
Contractor. J. A. Melland
Issued. 12-12-53

County Saline
KANSAS



CASING:

Elevation. 1308

8 5/8" OD 350' cem.w/250 sx, circ.
5 1/2" OD 3421 1/2' cem.w/60 sx

Production. IPP 201 B0 & 25% wtr

Figures indicate Bottom of Formations.

surface soil, shale	
and shells	345
Anhydrite	365
shale & shells	400
lime & shale	525
lime, shells & shale	740
shale & lime	910
shale & shells	1730
shale & lime	1930
lime	2055
shale & lime	2410
lime	2505
lime & shale	2745
lime	2830
lime & shale	2980
Miss. lime & chert	3010
lime	3095
lime & chert	3155
lime	3205
lime & shale	3423
Total depth, Rotary	

Scout Tops:	
Burgess sand	2908
Miss.	2911
Kinderhook	3202
Maquoketa shale	3358
Simpson dolomite	3421-23

Slope tests taken at regular intervals did not show any deflections from vertical.