

State Geological Survey  
WICHITA, BRANCH

STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

API # 15-053-20335

15-16-7W  
RECEIVED  
STATE CORPORATION COMMISSION

MAR 22 1974  
CONSERVATION DIVISION  
Wichita, Kansas

WELL LOG ----- KANAK #1  
Located: 100' S, 100' E, C W/2, Section 15-16S-7W, Ellsworth  
County, Kansas

OWNER: Glen Rupe  
ROTARY DRILLING CONTROLCATOR:: Sterling Drilling Company

COMMENCED: July 22, 1973  
COMPLETED: July 27, 1973

TOTAL DEPTH: 1845'

LOG

0 -	20	Clay
20 -	65	Sand and Gravel
65 -	219	Shale
219 -	330	Clay and Shale
330 -	875	Shale and Salt
875 -	1755	Lime and Shale
1755 -	1795	Lime, Shale and Sand
1795 -	1845	Shale and Lime

CASING RECORD

Ran 7 joints used 7" casing (214.11'),  
set at 213' G.L. with 100 sacks 60/40  
Pozmix with 3% cc. Plug down at 1:30 PM,  
7-22-73 by Sun.

Ran 60 joints 4 1/2" OD Casing, 1855'  
cemented at 1844' G.L. with 150 sacks  
50/50 Pozmix, salt saturated. Plug down  
at 8:00 PM, 7-27-73.

