



Lse #686 - KROBOTH #2 - C NW/4 of Section 16-16S-7W, Ellsworth County, Kansas

(53, SE, 1N, 1/4E <sup>14-156</sup> <sub>5</sub> Ellsworth, K)

Drilling Contractor: Red Tiger Drilling Company Rig #5 (913-625-7997) Registered  
Wichita, Kansas 67202 (263-2371) in Hays

Geologist: Wm G. Clement  
Wichita, Kansas

Garden Motel,  
Ellsworth  
Room 26 (913-472-3116)

Receiving on JL channel, Salina  
area - If can't reach, try  
Ellinwood or Russell

INVESTORS

- 2/9/76 Bill Clement gave Well location.  
2/12/76 Mailed "billing" for advance drilling.  
2/13/76 Mailed "Intent to Drill". Bill Clement ordered "elevation & staking  
with Laughlin-Simmons & Co.  
2/16/76 Laughlin & Simmons staked and ran elevation: 1541' Ground  
Red Tiger advised moving in 2/24/76 & 2/25/76 1546' Kelly Bushing  
2/26 *let part next week*  
2/28/76 Moved in & rigged up  
2/29/76 Spudded at 9:30 a.m. - 220' of 12 1/4" hole - Ran 9 joints of used 28# 85/8"  
Set at 217' along with 10' of landing joint  
Cemented with 160 sacks common - 2% gel, 3% Calcium Chloride - Cement did  
circulate  
Plug down at 2:45 p.m.  
Drilled plug at 8:45 p.m.  
3/1/76 7:00 a.m. - Drilling at 890'  
9:50 a.m. - Tops: Hollenberg 910' +636' Kelly B.  
Herrington 945' +601' "  
Running about 8' to 10' low on #1 Vondra  
Drilling at 962'  
3/2/76 8:40 a.m. Drillstem #1 1069'-1095'. Weak blow - dead in 10 min.. Open 15 min. *flush #2 dead in 3 min*  
Close 30 min., Open 5 min (No close). *Recovered* 10' mud. Init. flow -27, Final *to 30*  
flow 30. ISIP 239. 7:00 a.m. - Drilling @ 1410'  
10:30 a.m. Towanda 1067 - +479, Wreford 1241 - +294, Craus 1304 - +242  
3/3/76 Rotary, total depth -1775'. DST #2, 1739'-75'. Open 30, close 45, open 45,  
close 60. Good blow thru out. Recover: 10' mud, 300' muddy water.  
IF 55#, FF 212#. ISIP & FSIP - 670. Plugging today.  
3/3/76 Per Bill C. Tops: Wreford 1252 + 294, Neva 1445 +101, Red Eagle 1530 + 16,  
Grandhaven 1737 -191. RTD - 1775'. DST #2 1739-75. Open 30 - Close 45,  
Open 45 - Close 60. Strong blow thruout. Recover 10' mud, 300' muddy.  
INSI - 670. INF 55 to 129. FF 138 to 212. Temp. 89° D & A.  
FSL - 670.  
3/10/76 Called Red Tiger for Plugging information (Faye) Plugged with 25 sacks at 210';  
1/2 sack Hulls plug at 40', 10 sacks to Surface, 2 sacks in the rathole.  
Job completed 1:00 p.m. March 3, 1976