

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

500 East Murdock,

Wichita, Kansas

32-16-8W

Company CONTINENTAL OIL CO.
Farm-Hodgson "A" No. 2

SEC. 32 T. 16 R. 8W
CW/2 E/2 E/2 SE

1320' fr SL, 490' fr EL

SE $\frac{1}{4}$
County Ellsworth
KANSAS

Total Depth. 3339


Comm. 4-29-53

Comp. 5-10-53

Shot or Traced.

Contractor. Garvey Drilling Co.

Issued. 7-18-53



CASING:

9 5/8 set at 295' w/ 225 sx cement
5 1/2 set at 3333' w/ 150 sx cement

Elevation. 1668 RB

Production Pot. 55 BO, 198 SWPD

(Figures Indicate Bottom of Formations.)

sand rock	15
surface sand	72
shale	294
red rock	360
red bed & shale	680
anhydrite	700
shale & shells	800
salt, shale & shells	1000
lime & shale	1415
lime	1560
lime & shale	2430
shale	2440
lime	2581
lime & shale	2678
lime	3110
conglomerate	3133
lime & shale	3237
shale	3255
Simpson & conglomerate	3280
lime	3339
Total Depth	

TOPS:

Brown lime	2711
Lansing	2732
Conglomerate	3102
Maquoketa	3123
Viola	3163
Simpson	3212
Arbuckle	3284

Pay Arbuckle 3283-87