

32-16-8W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- CONTINENTAL OIL COMPANY
Farm- E. H. HODGSON No. 3
"A"

SEC. 32 T. 16 R. 8W
C SE
1320' frn SL, 1320' frn EL, SE $\frac{1}{4}$

Total Depth. 3911.5 SCH.
Comm. 9-29-53 Comp. 10-23-53
Shot or Treated.
Contractor. Anschutz Drlg Co.
Issued. 2-13-54

County Ellsworth
KANSAS



CASING:

9 5/8" 333' cem w/200 sx
5 1/2" 3411' cem w/400 sx

Elevation. 1684 R.B.

Production. SWDW

Figures Indicate Bottom of Formations.

shale, sand	65
shale, shells	300
redbed, shale, shells	340
Reaming 0-330	
shale, shells	1015
anhydrite	1040
shale, shells	1155
lime, shale	1315
lime	1490
shale, lime	1825
shale	2030
shale, shells	2295
lime	2625
shale, lime	2752
lime	3170
lime Viola	3201
Simpson	3245
lime	3287
lime, shale	3340
lime	3367
chert & lime	3470
lime	3508
lime, chert	3660
lime	3740
lime, sand, chert	3780
sand	3807
lime, chert, sand	3880
sand	3905
Total Depth	
T.D. (Sch.)	3911.5

Tops:

Lansing	2745
Maquoketa	3138
Viola	3240
Simpson	3301
Arbuckle	3351