

26-16-9W ✓


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MAYFIELD-SMITH DRILG., INC.
Farm- Gregory No. 1

SEC. 26 T. 16 R. 9W
SE SE NE

Total Depth. 3247'
Comm. 2-21-63 Comp. 3-2-63
Shot or Treated.
Contractor.
Issued. 7-13-63

County Ellsworth
KANSAS



CASING:
8 5/8" 265' cem w/140 sx.
5 1/2" 3243' cem w/100 sx.

Elevation. 1741' KB

Production. 57 BOPD, NW

Figures Indicate Bottom of Formations.

clay	70
sand & clay	85
clay, shells & shale	263
shale	518
anhydrite	525
shale	665
shale & shells	1100
shale & lime	1418
shale & shells	2435
lime & shale	2813
lime	3194
conglomerate	3230
lime	3247
Total Depth	

TOPS: (Corrected to Welex Guard Log.)

Topeka	2532
Heebner	2662
Toronto	2680
Brown Lime	2781
Lansing	2797
Base Kansas City	3094
Cherty Conglomerate	3154
Simpson Shale	3208
Simpson Sand	3216
Arbuckle	3241