

33-17-100


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

HERNDON DRILG.CO.
Stumps No. 4.

SEC.33 T.17 R.10W
CEL SE SW

Total Depth. 3302'
Comm. 9-17-41 Comp. 9-29-41
Shot or Treated.
Contractor.
Issued. 11-15-41

County. Ellsworth



CASING:
10 $\frac{3}{4}$ " 285' Cem.

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

surface soil & sand	65
shale & shells	520
anhydrite	545
shale & shells	890
salt	1135
shale & lime	1480
shale & shells	1600
sand	1635
lime	1670
shale & shells	1745
lime brkn	1850
shale & shells	1985
shale	2160
lime brkn	2265
shale & shells	2415
lime brkn	2515
shale & lime	2630
lime	2860
shale & shells	2910
lime brkn-Top of Lansing-	
KC limestone	2940
lime brkn	2955
lime	2983
colocastic limestone,	
very porous, no oil	
stain	2985
colocastic limestone,	
very porous, no oil	
stain	3148
lime	3181
lime & shale	3220
lime & shale-Top of	
Red shale conglomerate	3238
lime & shale-Top of	
Cherty&Sand Conglo.	3250
lime & shale	3255
lime-Top of Arbuckle	3276
chert white, no oil show	3286
oolitic dolomite	3287
dolomite cryst brownish	
showing slight porosity,	

no oil show	3300
lime & chert	3302
Total Depth.	