

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Location. SEc SW SE

Sec. 1 T. 17 R. 10W

Casing Record.

County. Ellsworth.

10" 1874 Farm. Stratmann
 20" 8" 2992 Company. J.A. Aylward et al.
 15" 385 65/8" 3161 Contr. J.A. Aylward.
 12" 543 53/16" Comm. 2-3-32
 Total Depth. 3290 Shot 40 Quarts Between 3237-3283
 Correspondence regarding this Well Should Be Referred To.

No. 3

Comp. 5-16-32



Elevation.

Initial Production.

40 bbls per hour.

Figures Indicate Bottom of Formations.

Date issued. 5-21-32

Formation	Depth	Formation	Depth	Formation	Depth.
cellar	12	red rock	1775	lime	3008
slate yellow	55	lime	1800	lime loose	3013
shale blk	95	red rock	1805	lime	3030
HW 60		red rock and lime		2 BWPHR 3030-3035	
shale	125	shells	1855	sand	3035
red rock	130	hole caving.		lime	3065
water sand	135	red rock	1866	lime	3115
shale	140	lime	1885	slate white	3120
shale blk	165	slate white	1890	lime	3175
sand	170	shale white	1900	shale blk	3180
slud yellow	190	lime	1920	lime hard	3205
shale blue	195	shale blk	1930	lime	3210
red rock	200	lime	1960	hole caving	3210
shale blue	370	shale white	1975	shale blk	3215
shale dark	400	lime	2025	lime	3220
shale blue	425	shale blue	2030	shale blue	3221
red rock	455	lime	2050	Conglomerate	3248
red rock	470	red rock	2060	shale green	3260
water sand	475	shale blk	2075	siliceous lime	3275
6 BWPHR from 470-475		lime	2100	1st oil at 3260. Cable Lead.	
red rock	530	shale blk	2115	Best pay from 3270-3280 Swabbed	
anhydrite	555	lime	2135	10 bbls per hr. oil Inc.	
red rock	770	red rock	2150	2 bbls at 3285. Well Plugged	
slate dark	780	lime	2185	back 4' with lead wool to	
lime	785	shale blk	2215	3286.	
slate dark	815	lime	2240	lime	3290
red rock	860	lime	2250	T.D.	
shale blk	965	shale blk	2260	+	
gyp	980	1/2 BWPHR 2260-2265		53/16 Liner 125.	
slate	1150	water sand	2265		
gyp	1200	slate	2305		
slate	1240	lime	2325		
shale blk	1255	slate blk	2335		
gyp	1260	lime	2355		
slate blk	1275	shale blk	2370		
lime	1290	lime	2380		
slate light	1300	shale blk	2440		
lime	1345	lime	2480		
shale blk	1370	shale blk	2490		
lime	1400	lime	2515		
slate	1420	shale blk	2535		
lime broken	1430	lime	2550		
lime	1455	2 BWPHR 2550-2555			
slate dark	1460	lime broken	2555		
shale blk	1470	lime	2600		
red rock	1485	shale blk	2610		
1 BWPHR 1545-1550		lime	2635		
lime	1625	shale	2640		
4 BWPHR 1590-1595		lime	2650		
red rock	1635	shale	2660		
lime	1670	lime	2845		
shale blue	1675	show of gas	2825-2845		
lime	1690	slate dark	2900		
shale blk	1695	lime	2905		
lime	1705	slate dark	2910		
red rock	1710	lime hard	2930		
lime	1720	lime	2945		
shale blue	1740	shale blk	2950		
red rock	1750	lime	2980		
lime	1765	shale blk	2990		

Hole caving.