


WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company - B & R, & DUWVE & FARRIS PRODUCTION CO.
Farm - Stratman No. 1

SEC. 1 T. 17 R. 10W
NE NE SW

Total Depth. 3260 PB 3156
Comm. 9-26-49 Comp. 10-6-49
Shot or Treated.
Contractor.
Issued. 9-23-50

County. Ellsworth
KANSAS



CASING:
8 5/8" 211' cem w/120 sx.
5 1/2" 3250' cem w/ 75 sx.

Elevation. 1798

Production. D & A

Figures Indicate Bottom of Formations.

surface clay, shale	211
clay, shale	416
red rock, shale	530
anhydrite	555
shale, shells	660
shale, shells, gyp	985
salt	1042
shale	1240
anhydrite	1280
shale, shells	1312
lime, shale	1700
shale	1820
shale, shells	1950
lime, shale	2570
lime	2835
shale, lime	2960
lime	2975
lime, shale	3055
lime	3110
lime, shale	3235
shale	3250
simpson	3252
arbuckle lime	3260
Total depth	
Plugged back	3156

Tops:
Topeka (Scout) 2590
Lansing K. C. 2924
Simpson Sand 3250
Arbuckle 3252

Perf. 3015-28 wtr / SSO