


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company ATLANTIC REFG. CO.
Farm Phelan No. 3

SEC. 2 T. 17 R. 10 W
NE NW SW

Total Depth. 3284
Comm. 11-4-45 Comp. 11-25-45
Shot or Treated. 1000 gals. acid.
Contractor. Noble Drlg. Co.
issued. 12-22-45

County. Ellsworth
KANSAS



CASING:
8 5/8" 325' Cem.
5 1/2" 3277' Cem.

Elevation. _____

Production. Temp. Allowable
25 BFD

Figures Indicate Bottom of Formations.

sand & red bed	0-30
shale & shells	815
anhydrite	874
shale & shells	1100
salt & shale	1190
shale & shells	1230
lime & shale	1426
lime	1507
shale	1647
lime	1850
shale & shells	1990
lime & shale	2151
sand & shale	2272
shale & shells	2405
lime & shale	2510
lime	2530
shale & shells	2610
lime	2740
shale	2755
lime	2868
lime & shale	2933
lime	3282
Drilled out cement & made 2' of new hole	3284
Total Depth.	

Acidized w/1000 gals.
Producing area 3277-84'

Tops:
Lansing 2945
Conglomerate 3257
Arbuckle 3268