

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - B & R DRLG. CO.
Farm - Breford No. 2

SEC. 3 T. 17 R. 10W
CS $\frac{1}{2}$ NE NE

Total Depth. 3287'

Comm. 10-6-46

Comp. 10-20-46

Shot or Treated.

Contractor.

Issued. 3-8-47

County. Ellsworth
KANSAS



CASING:

Elevation. _____

8 5/8" 300' com. w/175 sx.
5 1/2" 3267' com. w/ 50 sx.

Production. Phy. Pot. 234 Bbls.
plus 2% wtr.

Figures Indicate Bottom of Formations.

clay & sand	45
shale	90
sand	120
shale, shells & sand	220
sand & shells	280
shale & shell	300
shale blue	345
iron strks & shale	400
shale blue	420
red bed	567
anhydrite	590
shale	645
red bed & shale	765
red bed shale & shells	1015
salt	1135
salt & shale	1210
shale & shells	1300
lime & shale	1350
lime brkn & shale	1375
lime & shale	1475
lime sdy	1545
lime & shale	1600
lime	1660
lime sdy & shale	1720
lime	1775
lime sdy, shale	1830
shale & lime	2650
lime	3256
Conglomerate	3268
Arbuckle	3270
Corr. to D. F.	3268
lime	3287
Total Depth	