

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
 508 E. Murdock, Wichita, Kansas.

Company - CITIES SERVICE OIL CO.  
 Farm - Stoltenberg "C" No. 1

SEC. 4 T. 17 R. 10W  
 NE NE NE  
 330' S & 330' W of NE cor.

Total Depth. 3297  
 Comm. 12-3-49 Comp. 1-5-50  
 Shot or Treated. 5000 gals. acid  
 Contractor. Holm-Louis Drlg.  
 Issued. 2-25-50

County. Ellsworth  
 KANSAS



Elevation. \_\_\_\_\_

Production. Pumped 103 oil, trace  
 wtr, 2 1/2 hrs

CASING:  
 8 5/8" 314' cem. w/175 sx.  
 5 1/2" 3271' cem. w/125 sx.

Figures Indicate Bottom of Formations.

shale & shells	220
lime & shale	315
shells & shale	530
shale	590
anhyd.	620
shale	1040
salt	1200
shale & shells	1340
lime & shale	1755
shale & shells	1920
shale	2510
lime & shale	2710
lime	2825
lime & shale	2965
lime RTD	3270
3270 = 3271 SLM	
lime	3297
Total Depth	

Tops:  
 Corr. Lansing 2962  
 Corr. Arbuckle 3268

Pen. 29'

25' oil in 11 hrs. at 3293

12-21-49 Acidized 1000 gals.  
 12-23-49 " 3000 " acid.  
 went around shoe

Plugged back w/sand 3293-3276  
 and 3276-73 with cem.

Set retainer at 3237 & squeezed w/200  
 sx cem.; 176 sx around shoe at 1600#.

Drilled cem. & cleaned out 3293.

1-4-50 Tried to acidize; formation would  
 not take acid.  
 1-5-50 Deepened 3293-97.  
 4 gals. oil in 3 1/2 hrs.

Shot 20 qts. 3381-93.

1-7-50 Acidized 1000 gl.s