

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CITIES SERVICE OIL

FARM Stoltenberg "C" NO. 2

SEC. 4 T. 17 R. 10W

LOC. SE NE NE

990' South & 330' West of NEC

TOTAL DEPTH 3292

COMM. 9-15-50


COMP. 10-4-50

SHOT OR TREATED

CONTRACTOR Barbour D^hlg. Co.

ISSUED 12-9-50

COUNTY Ellsworth
KANSAS



CASING

8 5/8" 331' cem. w/175 sx
5 1/2" 3274' cem. w/150 sx

ELEVATION 1822

PRODUCTION P. 20 BOPD & NW

FIGURES INDICATE BOTTOM OF FORMATIONS

clay	40
shale	260
shale & redbed	570
anhydrite	640
redbed, shale & salt	1045
salt & shale	1254
shale & shells	1270
shale	1350
lime & shale	1485
shale & shells	1635
lime & shale	2195
shale	2635
lime	2935
lime & shale	3005
lime	3255
shale & lime	3281
3281 RTD ~-3276 SLM	
lime	3292
Total depth	

Tops:

Lansing Corr.	2962
Cherty Congl. Corr.	3264
Arbuckle Corr.	3273
Penetration	19'
Elevation 1822 (1819 Gr.)	

Remarks:

20' oil in 1 hr. at 3283
125' oil in 13 hrs. at 3283
10-3-50 Acidized 1000 gals.
10-4-50 Deepened 3283-92;
70' oil in 1 hr.
Shot with 20 qts. 3280-89.
10-9-50 Acidized 2500 gals.