

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY THE CARL TODD DRILLING COMPANY

SEC. 7 T. 17 R. 10W

FARM Frevert

NO. 1

LOC. NW NW NE

TOTAL DEPTH 336 1/2

COMM. 12-15-50

COMP. 1-19-51

SHOT OR TREATED

CONTRACTOR

ISSUED 2-17-51

COUNTY Ellsworth

KANSAS



CASING

8 5/8" 225' cem. w/165 sx
5 1/2" 3352' cem. w/100 sx

ELEVATION 1910 DF

PRODUCTION Dry

FIGURES INDICATE BOTTOM OF FORMATIONS

surface clay rock	60
shale, shells	225
sand	235
shale, shells	350
red bed, shells	685
anhydrite (hard)	710
shale, shells	1340
shale, lime	2770
lime	2905
lime, shale	3060
lime	3347
conglomerate	3352
arbuckle, RTD	3360 1/2
dolomite	3376 1/2
Total Depth	

Tops: R.B.

Heebner Shale	2932
Base Oread	2967
Brown Lime	3036
Lansing	3052
Chert Conglomerate	3347
Arbuckle	3352

Acidized w/500 gals. at 3367, no show. Acid circ. shoe. Then D.D. to 3373 w/no show. 3373-75 one bbls. oil per hr. nat. 375-76 1/2 no inc. Bridged hole & squeezed w/250 sx. cem. Drilled out 3376. 500 gals. acid no inc. Acid circ. shoe or hole in pipe. 1000 gals. acid thro tubing w/packer, no inc. Cem. 4 1/2" liner at 3362. Drilled out 3376 1/2. 1000 gals. acid thro tubing & packer in 4 1/2" liner. Acid circ. liner, no inc.