

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - LAUCK & MONCRIEF
Farm - Frevert No. 2.

SEC. 11 T. 17 R. 10 W
NE NW SW

Total Depth. 3294
Comm. 5-24-45
Shot or Treated.
Contractor.
Issued. 7-28-45

Comp. 6-18-45

County. Ellsworth
KANSAS



CASING:
10" 189' Cem.
5" 3243' Cem.

Elevation. _____

Production. Pot. 181 B Pump.

Figures Indicate Bottom of Formations.

surface	185
red rock	335
sand	357
red rock	550
lime brkn	636
shale & shells	1275
shale sdy & lime	1614
lime sdy	1640
shale sdy & lime	1659
shale & lime	1885
lime	2062
shale	2103
shale & lime	2343
lime	2450
lime & shale	2563
lime	2665
shale & lime	2792
shale	2909
lime	3018

Temp. Prod. est. June 16, 1945

Permanent July 16, 1945
181 Bbls Pump.

Tops: DF
Brown lime 2908
White lime 2934
Conglomerate 3242
Arbuckle 3245

2923 - 2933
lime 3239
Arbuckle 3244
standardized
3239 - 3243
3244 - 3248

lime 3252
lime sft 3254
show oil
lime sft 3255
lime hrd 3258
free oil
lime sft 3261
increase oil
lime sft 3264
increase oil
lime hrd 3266
swab $1\frac{1}{4}$ BPH for 2 hrs
lime hrd 3267
lime sft 3270
increase oil
lime sft 3273
increase oil
1000' oil swab 10 B
1st hr, $6\frac{1}{2}$ B 2nd hr.

lime 3276
lime sft 3279
increase oil
1750' oil
lime 3285
increase oil
lime & green shale 3290
lime sft 3293
increase oil
lime 3294

swab 1st hr $18\frac{3}{4}$ B
2nd hr $18\frac{3}{4}$ B
3rd hr $16\frac{1}{4}$ B
Total Depth