


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - D. R. LAUCK OIL CO., INC.
Farm - Frevert No. 4

SEC. 11 T. 17 R. 10W
SWc NE SW

Total Depth. 3266 PB 3261 $\frac{1}{2}$
Comm. 5-27-49 Comp. 6-17-49
Shot or Treated.
Contractor.
Issued. 7-16-49

County. Ellsworth
KANSAS



CASING:
8" 150 cem 150 sx
5" 3230 cem 75 sx

Elevation. _____

Production. Est. 100 bbl

Figures Indicate Bottom of Formations.

surface, shale	115
sand	130
shale, shells	525
limo	540
shale, shells	1030
salt, shale	1240
limo, shale	1610
limo	1705
limo, shale	1920
shale, shells	2110
shale, limo	2575
limo	2825
shale, limo	2895
limo	3235
standardized	
top arbuckle dorrick fl	3230
rotary total depth	3233
limo	3234
limo rainbow	3237
limo free oil	3240
limo	3243
limo	3246
increase oil	
limo	3249
limo	3252
limo	3255
increase oil	
limo	3258
increase oil	
limo	3261
increase oil	
1750 oil	
swab 6 $\frac{1}{2}$ bbl hr for 3 hr	
limo dome water	3266
Total Depth	
PB 3261 $\frac{1}{2}$	
completed	

TOPS:

Hoobner	2788
Brown Limc	2892
White Limc	2918
Conglomerate	3217
Arbuckle	3230