


WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - D. R. LAUCK OIL COMPANY
Farm - Frevert No. 5

SEC. 11 T. 17 R. 10W
SW SE NW

Total Depth. 3318 DF PB 3296
Comm. 6-12-49 Comp. 7-2-49
Shot or Treated. Acid
Contractor.
Issued. 8-6-49

County. Ellsworth
KANSAS



Elevation. _____

Production. Est. 100 bbls.

CASING:

8" 192' cem w/150 sx.
5" 3318' cem w/75 sx.

Figures Indicate Bottom of Formations.

surface	90
sand	120
shale, shells	305
sand, iron	350
shale, shells	990
anhydrite	1025
shale, salt	1240
lime, shale	2560
lime	3320
Standardized:	
Top Arbuckle DF	3246
Total depth DF	3318
Total Depth DF	
PB 3296	
Tops: DF	
Heebner	2796
Brown li e	2901
White line	2928
Conglomerate	3230
Arbuckle	3246

Ran Gamma Ray
Lane Wells total depth 3296½
Perforated 3250-65, 75 shots,
acidized 1000 gallons.
Lots water & some oil
Squeeze 50 sx. cement
 30 sx. going into formation.
Drilled cement to 3296.
Perforated 3250-64, 46 shots
Acid: 1000 gallons, ½ bbl pr hr.
Perforated 3269-75, 75 shots,
Swb 6 bbl pr hr for 4 hrs.
complete Est. 100 bbls.
DST 3251-76, 30" 750' oil
DST 3287-3300'
20" 900' water