


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - D. R. LAUCK OIL CO., ETAL
Farm - Frevert No. 6

SEC. 11 T. 17 R. 10W
SE SW NW

Total Depth. 3599
Comm. 6-25-49 Comp. 7-12-49
Shot or Treated.
Contractor.
Issued. 8-6-49

County. Ellsworth
KANSAS



CASING:
10" 202' cem w/150 sx.
5" 3336' cem w/100 sx.

Elevation. _____

Production. S.W.D.W.

Figures Indicate Bottom of Formations.

clay, shale	120
sand	135
shale, shells	310
sand, iron	350
shale, shells	1050
salt, shale	1175
shale, shells	1603
lime	1630
lime, shale	2180
shale	2245
lime, shale	2580
lime	3220
conglomerate	3264
lime	3600

Standardized:

Total Depth DF 3598

lime 3599

Total Depth

Tops: D.F.

Heebner 2801

Brown Lime 2906

White Lime 2930

Conglomerate 3239

Arbuckle 3261

DST 3266-80, 1 hr 75' oil cut mud.

DST 3266-93, 30", 110' water and
little oil cut mud.

Salt water disposal well, took 178
bbls in 55 mins.