

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.

UNION NATIONAL BANK BLDG, WICHITA, KANSAS


Location. NW NE NE

Sec 12 T. 17 R. 10W

Casing Record.
 wood don. 20' 10" 1895 Farm. Stratman
 20" 8 1/4" 3059 Company. Smith and Ash-Derby.
 15 1/2" 355 65/8 3187 Contr.
 12 1/2" 531 53/16" 119 Comm. 4-2-32
 Total Depth. 3282 1/2' Shot Quarts Between.
 Correspondence Regarding This Well Should Be Referred To.

County. Ellsworth.
No. 1

Comp. 5-6-32



Elevation.

Figures Indicate Bottom of Formations.

Initial Production.

Date Issued. 6-25-32

Swab 75 bbls per hr.

Formation	Depth	Formation	Depth	Formation	Depth.
cellar	12	shale	1902	lime	3080
myd yellow	30	broken lime	1925	shale blue	3088
sdv lime HFW	40	slate	1955	lime	3130
lime	45	lime	1980	show oil 3100-3110	
water sand	60	shale	1987	sdv lime 1/3 BW	3140
mud yellow	88	lime	2015	sdv lime 1 1/2 BW 56 -	3162
slate blue	185	slate white	2035	lime	3190
red mud	190	slate blue	2095	slate	3195
lime	200	lime	2101	lime	3218
slate	239	shale blue	2124	slate blk	3224
lime	249	lime	2128	lime brown	3229
slate blue	267	shale blue	2140	slate blue	3235
lime grey	275	lime	2150	conglomerate	3250
slate blue	285	shale blue	2175	shale green	3259
red sand Prob wtr	300	slate pink	2185	sand show oil	3263
lime	305	slate blk	2195	Corrected Meas.	3260 1/2
slate blue	332	slate blue	2245	equals	3263
sand Prob. water	347	lime	2270	Sil lime	3275 1/2
shale blue	410	slate blk	2280	set 53/16 liner 3257 1/2 Corr.	
red rock 5BW 435	515	sdv shale	2300	measurement.	
anhydrite	524	slate blue	2315	shale break	3277 1/2
lime brown	536	lime	2330	Sil lime	3282 1/2
slate blue	545	slate blk	2336	T.D. Cable Measurement.	
red rock	600	lime grey	2347		
slate blue	650	shale blue	2356	Hole filled up 3000' in	
red rock	745	lime	2370	9 hours at 3264 1/2	
shale blue	870	slate blk	2382	Swabbed 35 bbls per hr	
slate white	880	shale blue	2388	400' off bottom.	
slate blue	975	lime	2410	Swabbed 45 bbls per hr	
salt	1265	shale	2460	3275 1/2 - 600 ft off bottom.	
broken lime	1315	lime broken	2490	swabbed 75 bbls per hr	
lime hard	1350	shale blue	2500	1400' off bottom 3282 1/2	
broken lime	1409	lime	2525		
slate blue	1423	shale blue	2550		
lime	1475	lime	2610		
red rock	1485	shale blue	2618		
lime	1510	lime	2650		
shale blue	1535	lime	2667		
lime	1615	shale blue	2673		
1/2 BW 1565 1B 1600		lime	2805		
sdv lime 3BW	1630	slate blk	2809		
red rock	1638	lime	2814		
lime	1695	shale blue	2820		
shale blk	1702	lime	2833		
lime	1714	shale brown	2837		
shale blue	1722	red rock	2862		
lime broken	1770	M.G 2864			
slate blk	1775	lime	2884		
red rock	1784	shale blue	2922		
lime	1810	lime	2965		
shale blue	1814	shale blk	2974		
lime	1860	lime brown	2998		
red rock	1872	shale blue	3002		
lime	1883	lime	3040		
shale	1892	6 BW 40-57 show oil	3040-45		
lime	1900	sdv lime	3057		