


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - BAY PETRO. CORP.
Farm - Wilkens No. 2.

SEC. 13 T. 17 R. 10 W
CSL NE NE

Total Depth. 3239
Comm. 12-1-44 Comp. 4-14-45
Shot or Treated.
Contractor.
Issued. 5-26-45

County. Ellsworth
KANSAS



CASING:
8 5/8" 422'
5" 3233'

Elevation. _____

Production. Pot. 107 BOPD

Figures Indicate Bottom of Formations.

surface clay	0-90
shale & shells	290
sand & shells	315
shale & shells	525
anhydrite	545
shale & shells	1000
salt & shale	1175
shale & shells	1290
shale & lime	1385
anhydrite	1400
shale & lime	1600
lime	1720
shale & lime	1805
lime brkn	1836
shale	1852
shale & lime	2100
lime	2132
shale	2223
lime	2233
shale	2253
shale & lime	2330
lime brkn	2354
shale & lime	2437
shale	2520
lime	2766
shale & lime	2880
shale	2910
lime	3209
conglomerate	3233
lime	3239
Total Depth	

Tops:

Anhydrite	520-45
Brown Lansing	2904
White Lansing	2996
Conglomerate	3222
Arbuckle	3231

Sh of oil 3233-35

Drilled Plug 3239TD
Fill up 385' Oil in 7 hrs.
Est. 1 1/4 BOPH

500 Acid Swb - 3 BOPH
1000 Acid - Did not break down
I.P. 107 BOPH