


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - DUWE & FARRIS  
Farm - Wilkins No. 2.

SEC. 13 T. 17 R. 10 W  
C N  $\frac{1}{2}$  SW NE

Total Depth. 3241'  
Comm. 2-25-44 Comp. 3-8-44  
Shot or Treated.  
Contractor. Royer-Farris Drlg.Co.  
Issued. 12-2-44

County. Ellsworth  
KANSAS



CASING:  
8 5/8" 204'4" Cem.  
5" 3226'

Elevation. \_\_\_\_\_

Production. Pot. 40 B.

Figures Indicate Bottom of Formations.

sand	10	lime xlyn	3160
shale	93	lime xlyn & fine	
sand	123	solid oolitic	3165
shale	129	shale red & dk gry	3170
shale hd	143	xlyn lime & chert	3185
shale & shells	990	xlyn lime	3197
salt & shells	1200	shale gry, red, pale	
lime shells & shale	1315	green	3200
lime & shale	1695	lime fossiliferous	3205
lime	1785	shale red & gry	3210
lime brkn & shale	1955	lime	3218
lime	1985	shale red & green w/	
shale & lime shells	2075	varicolored chert	
shale & shells	2290	pebbles	3221
shale	2325	shale bright grn w/	
lime	2345	little sand & pyrite	
shale	2355	pyrite	3224
lime & shale	2433	xlyn, dolomite slightly	
lime	2527	cherty w/fair to good	
shale	2565	por w/some staining	
lime	2790	by lgt brwn oil	3227
lime	2824	Total Depth drilled by	
sandstone-shaly at		Rotary	
base	2853	Cable Tools:	
shale & lime	2895	dolomite w/lgt oil	
lime hd	2901	stain	3229
lime	2907	dolomite xlyn w/little	
shale red & pale grn	2917	porosity & light	
lime w/some chert	2934	oil stain	3232
lime porous & solid		dolomite w/very little	
oolitic - no oil	2941	porosity & lgt oil	
lime	2955	stain	3234
xlyn & lime solid		dolomite	3236
ool. cherty @ top	2965	cherty dolo. w/some	
xlyn lime	2980	sand grains	3238
lime gy: lgt gy fine		dolomite & chert	3239
xlyn partly cherty	2990	xlyn dolomite w/much	
xlyn lime	3000	chert dk gry &	
lime porous sft		almost blk	3241
oolitic	3023	Total Depth.	
xlyn lime lgt gry fine	3035	Tops:	
xlyn lime dk gry fine	3040	Dodge Lime	2895
shale	3048	Lansing KC Ls	2917
clyn lime	3075	Base KC Ls	3197
lime xlyn &		Cherty Congl	3218
solid oolitic	3085	Simpson Form.	3221
xlyn lime	3095	Arbuckle Dolo.	3224
lime oolitic & fine			
xlyn	3102		
xlyn lime	3104		
lime porous & solid			
oolitic w/few sli.			
spotted oil stains	3108		
lime xlyn	3125		
shale red & blk	3130		
lime	3140		
lime w/little pink			
chert	3150		