


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

VICKERS PETROLEUM CO.
Peterson No. 1

SEC. 14 T. 17 R. 10W.
CNL NE NE

Total Depth. 3291 $\frac{1}{2}$
Comm. 8-22-40 Comp. 10-6-40
Shot or Treated.
Contractor. Jayhawk Oil Co.
Issued. 10-26-40

County Ellsworth.



CASING.

103/4" 221' cemented.
5 1/2" 3263 1/2 cemented.

Elevation.

Production. Min well.

Figures Indicate Bottom of Formations.

surface	222	Acidized 1000 gal. pumped 23 bbls oil
broken sand & shale	395	after head 12 hours.
red bed	415	
red bed sand&pyrite	445	Sept 15, 1940. Jetted 1000 gal acid.
pyrite	450	potential 16 WOPD
broken red bed and		Sept. 23, 1940. Jetted 780 gal acid-no help.
shale	520	
shale and shells	542	
anhydrite	563	
red bed and shale	840	
shale and shells	1020	
shale and salt	1258	
anhydrite	1310	
broken lime & shale	1335	
lime	1400	
lime & anhydrite	1465	
lime and shale	1655	
lime	1800	
shale and lime	2332	
lime	2350	
broken lime	2356	
shale and lime	2605	
lime	2850	
broken lime	2865	
shale and lime	2934	
lime	2975	
broken lime	3130	
lime	3270	
T.D. Rotary hole.		
RUST		
Drilled plug.		
cherty lime	3281	
some oil		
cherty lime	3284	
more oil		
lime	3286	
750' oil 8 hours swabbed		
down filled 60' in 1 hour.		
lime	3291 $\frac{1}{2}$	
Total Depth.		
Ino. in oil Est. 3 bbls		
per hour. Show water.		
completed for Min. Well.		