


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- THE EL DORADO REFG. CO.  
Farm- Myers No. 1

SEC. 18 T. 17 R. 10W  
NW NW NW

Total Depth. 3259  
Comm. 10-2-51 Comp. 10-13-51  
Shot or Treated.  
Contractor. Sterling Drlg. Co.  
Issued. 12-22-51

County Ellsworth  
KANSAS



CASING:  
8 5/8" 316' cem w/150 sxs.  
5 1/2" OD 3250' cem w/85 sxs.

Elevation. 1869 DF

Production. 154 BOPD & 20% wtr.

Figures Indicate Bottom of Formations.

shale, shells	640
anhydrite	665
shale, shells	1350
shale, lime	1670
lime	2010
broken lime	2110
shale, lime	2665
lime	2785
lime, chert	2845
lime	2895
shale	2965
lime	3245
quartzite	3252
quartzite	3259
Total depth	

Tops: DF	
Huebner	2857
Brown Lime	2959
Lansing	2975
Pro-Cam qtz.	3245

DST 3004-34, gas to surf/  
15 min., op 30 min. rec. 35' GGM,  
est. 1/4 mil CFG  
DST 3060-83, op. 30 min. rec. 255'  
O & CCM & 30' salt wtr.  
DST 3148-56, op. 30 min. rec.  
10' mud, no BHP  
C. O. & D D 3256 rainbow SO  
in hard quartzite. DD 3259TD  
in very hard quartzite, ran  
Gamma Ray log, no por. in qtz.  
Perf. (9) 3153-56, 1000 acid FU  
1200-1400' oil; est 15-25 BOPH  
Plug @ 3100; Perf. 3065-74,  
tested 9-9 GPPH mostly clear &  
salty wtr. Squeezed & C O  
re-acid. 3000 gals. est 5 BO & 2  
BWPB  
Producing from 3153-56