

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company - INGLING ET AL
Farm - Murray No. 1

SEC. 18 T. 17 R. 10 W
NEo NE

DISCOVERY WELL

Total Depth. 3332'
Comm. 5-20-44 Comp. 6-6-44
Shot or Treated.
Contractor. Donald T. Ingling
Issued. 8-26-44

County. Ellsworth
KANSAS



CASING:
8 5/8" 221'
5 1/2" 3311'

Elevation. _____

Production. Est. 100 B.

Figures Indicate Bottom of Formations.

surface clay & sand	0-75
shale-red clay & sand	195
shale & lime shells	221
red bed, shale & shells	690
anhydrite	740
shale & shells	1080
salt & shale	1195
shale & shells	1250
shale, shells & red rock	1290
sandy lime	1380
sandy lime & shale	1585
sandy lime, shale & red rock	1710
sandy lime	1805
lime & shale	2200
shells & shale	2290
shale & lime	2390
broken lime	2625
lime	2680
cherty lime	2785
lime & shale	2810
hard dense lime	2830
lime-cherty streaks	2855
lime	2887
lime & shale	2915
lime	3291
cherty lime (very rough)	3293
cherty cong.	3309
lime	3311
Arbuckle - T.D. rotary - - - - -	3332
Total Depth.	

Tops: K. C. 3003
Conglomerate 3291
Arbuckle 3309