


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- IMPERIAL DRILLING COMPANY, INC.  
Farm- Jake Secrest No. 1

SEC. 20 T. 17 R. 10W  
SW NW SE

Total Depth. 3325  
Comm. 2-22-52 Comp. 3-13-52  
Shot or Treated.  
Contractor. Imperial Drlg Co., Inc.  
Issued. 4-5-52

County Ellsworth  
KANSAS



Elevation. 1821 L.R.B.

Production. dry

CASING:

8 5/8" 2241' cem w/125 sx  
5 1/2" 3290' cem w/ 75 sx

Figures Indicate Bottom of Formations.

surface clay, rock sand	60	
shale, shells	390	
red bed, shells	580	
anhydrite	610	
shale, shells	1350	
lime, shale	2035	
lime, shells	2165	
shale, lime	2645	
lime	2850	
lime, shale	2975	
lime K. C.	3020	
lime	3297	RTD
lime	3325	
Total Depth		

Tops:

Heebner	2852
Brown Lime	2955
Lansing	2975
Conglomerate	3248
Eros. Arb.	3283
Arb. Dolomite	3290

D.S.T. 3017-3037, open 1 hr;  
light blow throughout; recovered  
12' slightly gassy. mud; 15 min.  
SIBHP 0#.

DST 3284-3297, open 35 mins.;  
weak blow died in 5 mins., rec.  
6' mud with no show; 15 min  
SIBHP 560#.