


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

ATLANTIC REFG. CO.
Stratmann No. 1.

SEC. 23 T. 17 R. 10 W
CN $\frac{1}{2}$ NE NE
30'E of CN $\frac{1}{2}$ NE $\frac{1}{4}$ NE $\frac{1}{4}$

Total Depth. 3239'
Comm. 3-20-42 Comp. 4-9-42
Shot or Treated.
Contractor.

County. Ellsworth



Issued. 6-27-42 Rotary O-3231
Cable 3231-39

CASING:
8 5/8" 281' Cem.
6 1/2" 3224' Cem.

Elevation.

Production. Temporary Pot. 85 Bbls.

Figures Indicate Bottom of Formations.

shells, red bed, sand	0-185
red bed, lime shells	285
shale, red rock, shells	620
shale & shells	720
anhydrite	745
shales & shells	835
shale	975
shale, salt	1135
salt & shale	1210
lime & shale	1315
lime & shale	1390
lime	1435
shale	1587
lime & shale	1625
lime	1715
shale	1755
shale & shells	1865
lime & shale	1950
lime	2035
shale, shells	2135
shale	2350
shale & shells	2470
shale	2525
lime	2810
shale	2870
shale, lime	2910
lime & shale	2941
lime	2975
lime & shale	3050
lime	3200
lime chert	3221

Cored, rec. 4 $\frac{1}{8}$ ' 3221-26

2' shale
6" blk chert
2' dolomite, hd dense

Cored, rec. 4 $\frac{1}{8}$ ' 3226-3231

1' hd tight dolomite
2' 6" dolomite, some grn
shale
1' dolomite

lime	3235
lime hd	3237
lime	3239

Total Depth.

Shot formation w/4 Qts. 3228-34
Acidized w/1000 Gals., Tested
28 $\frac{1}{2}$ BO, no wtr in 8 hrs.
Producing zone 3228-39

Sample Tops: Lansing 2915
Arbuckle 3224