

UNION NATIONAL BANK BLDG WICHITA, KANSAS


Location. SWc SW

Sec 24 T. 17 R. 10W.

Casing Record.

County. Ellsworth

10" 1810 Farm. Shonyo No. 1
 20" 8" 2527 Company. Smith-Ash and Gypsy Oil Co.
 15¹/₂" 305 65/8" 3081 Contr. Smith-Ash
 12³/₄" 487 53/16" 3239 Comm. 1-18-33 Comp. 3-10-33
 Total Depth. 3269 Shot Quarts Between.
 Correspondence Regarding This Well Should Be Referred To.



Elevation.

Figures Indicate Bottom of Formations.

Initial Production.

Date Issued. 4-1-33

Pot 340 bbls.

Formation	Depth	Formation	Depth	Formation	Depth.
cellar	8	shale blue	1780	lime	3075
clay red	32	red rock	1810	shale blue	3080
sand HW	110	lime	1813	lime	3122
shale blue	125	red rock	1827	shale grey	3126
shale red	130	lime	1875	lime	3158
mud blue	165	shale grey	1920	broken lime	3162
slate white	215	lime	1980	lime	3193
shale grey	225	shale blue	1987	shale blk	3205
shale blue	243	lime	2015	conglomerate	3239
lime	260	shale blue	2060	lime	3242
shale blue	268	cave 2015-2060		Sil lime	3263
lime	282	lime	2068	Blk break	3267
sdv lime	289	shale blue	2090	Sil lime	3269
lime	300	red rock	2100	TD.	
shale blue	335	lime	2118		
lime	347	shale grey	2122	1st show oil	3252.
red rock	491	sdv lime	2130	1st free oil	3255
anhydrite	510	lime	2147	Gradual increase	3263.
shale blue	514	Gas 2147-2150		2nd pay showed increase	3267-69
red rock	710	broken lime	2150		
lime shell	713	shale blk	2210	1st oil at 2PM 175' oil in	
shale blue	790	lime	2230	hole at 3:30 depth 3261.	
red rock	822	shale blue	2278	At 5:30 P.M. 800' oil in	
shale blue	940	lime	2302	hole at 3264	
salt	1187	shale	2306	at 7:00 P.M. 1075' oil in	
shale blue	1194	lime	2315	hole 3268	
lime shell	1200	shale blue	2320	at 8:00 P.M. 1400' oil in	
shale grey	1215	lime	2337	hole depth 3269	
lime	1220	shale blue	2344	at 8:30 P.M. 1770' oil in	
slate blue	1245	lime sdv	2350	hole.	
lime shell	1255	shale blk	2354	at 9:30 P.M. 2035' oil in	
shale blue	1260	lime	2362	hole. actual measurements.	
lime	1283	shale blue	2380		
shale blue	1295	lime	2384		
lime	1302	shale blue	2425		
shale blue	1320	lime	2436		
red rock	1325	shale blue	2440		
lime	1332	lime	2450		
shale blue	1385	shale grey	2465		
lime	1421	lime	2482		
small show gas 1415.		shale blk	2511		
shale blue	1430	more gas 2511-18			
red rock	1448	663,600 M.			
lime	1470	sdv lime	2518		
shale blue	1495	lime hard	2630		
lime 1BW 1500-10	1530	shale grey	2648		
shale blue	1540	lime	2665		
sdv lime 5BW 1560-70	1577	slate	2670		
shale blue	1595	lime 1/2BW 2712-20	2790		
red rock	1600	shale grey	2795		
lime sdv	1608	lime	2810		
shale blue	1640	red rock	2820		
gritty lime	1665	shale blue	2838		
slate blk	1673	red rock	2868		
lime	1680	shale	2890		
shale blue	1685	red rock	2892		
red rock	1700	lime	2899		
shale blue	1720	shale blue	2902		
red rock	1725	K.C. lime	2970		
lime	1737	shale blue	2974		
shale blue	1745	lime 4BW 3005-15	3054		
red rock	1755	shale blue	3060		
lime	1771				