


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company. BUICK DRILLING INC., ET AL  
Farm. Stumps "A" No. 2

SEC. 25 T. 17 R. 10W  
SE SE NE

Total Depth. 3215'  
Comm. 7-26-58 Comp. 8-9-58  
Shot or Treated.  
Contractor. Buick Drlg. Inc.  
Issued. 4-11-59

County Ellsworth  
KANSAS



CASING:

8 5/8" 223' cem w/125 sx.  
5 1/2" 3209'

Elevation. 1759' KU

Production. 25 BOPD

Figures indicate Bottom of Formations.

surface clay	20
sand	40
yellow clay	120
blue clay sandy	217
blue clay	250
sand	278
blue clay	320
white clay	335
red bed	482
Anhydrite	515
shale & shells	750
dark gray & blue lime (some anhydrite)	785
shale & shells	1160
lime and shale	1350
lime	1615
lime and shale	2080
shale	2485
lime	2795
lime and shale	2860
	3110
lime and shale	3209
lime	3215 RTD
Total Depth	

TOPS:

Anhydrite (driller)	482
Heebner Shale	2743
Toronto Lime	2764
Douglas Shale	2774
Iatan Lime	2860
Lansing	2876
Base Kansas City	3126
Marmaton	3136
Conglomerate	3196
Arbuckle	3208

DST 2902-2911', op 1 hr, produced a strong  
declining blow; rec. 30' mud, no shows,  
BHP 40#/20 min., IF - FF 25#; HH 1595#.