


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SKELLY OIL CO.
Farm-John Stumps No. 5

SEC. 25 T. 17 R. 10W
NW SE SE
990' fr SL 990' fr EL SE/4

Total Depth. 3270 PBTB 3265
Comm. 5-8-53 Comp. 5-23-53
Shot or Treated.
Contractor. Claude Wentworth Drilling Co., Inc.
Issued. 7-25-53

County Ellsworth
KANSAS



Elevation. 1753 DF

Production. Pot. 232 BO, no W

CASING:

8 5/8 set at 500' w/ 325 sx cement
5 1/2 set at 3269' w/ 400 sx cement

Figures indicate Bottom of Formations.

surface soil, clay & sand	40
shale & shells	400
red bed & shells	490
anhydrite	525
red bed, shale & shells	900
salt	975
salt, shale & shells	1350
lime & shale	2525
lime	2785
sand	2802
siltstone & sand	2804
sand & lime	2876
shale & lime	2893
lime	3199
shale w/ sand grains	3233
dolomite	3270
Total Depth	

TOPS:

Anhydrite	487
Heebner	2758
Toronto	2777
Douglas sand	2789
Brown lime	2872
Lansing	2893
Conglomerate	3199
Arbuckle	3235

Ran Gamma Ray Survey & Perf. csg.
3227-31 2/ 25 holes; GSO-free.
B & T 2 hrs. 2 BOPH, no wtr. Swbd OB
2 hrs, 2 BOPH, no wtr. Perf. 3209-27
w/ 106 holes, 3202-06 w/ 25 holes.
500' oil in hole while perf. no wtr.
Swbd OB 20 hrs, 213 BO no wtr,
Swbd 5 1/2 hrs, 59 BO, no wtr. Bailed
hole clean & ran tubing & rods.
Installed reg pmpng equip, FOB 8 hrs
on PPT, 77.22 BO, no wtr to establish
SCC pot.

Prod. form. Conglomerate 3202-3231
Sight odor of oil 3199-3233

D.S.T, Halliburton packer set at 2786 open
1 hr, rec, 20' of drilling mud. BHP 0#.
D.S.T, Halliburton packer set at 2907 open 1
hr, rec, 545' of heavy oil and gas cut
mud and 180' muddy oil, BHP 275#.