

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

GULF OIL CORPORATION.
Carrie K. Janssen No. 2

SEC. 29 T. 17 R. 10W.
CE $\frac{1}{2}$ NE SW

Total Depth. 3332
Comm. 3-20-41 Comp. 4-4-41
Shot or Treated.
Contractor.
Issued. 6-14-41

County Ellsworth.



CASING.

85/8" 219' cemented.

Elevation.

Production. Dry.

Figures Indicate Bottom of Formations.

shale and sand	221
red bed	300
shale and red bed	525
shale red rock and sand	675
red bed and shale	970
shale and salt	1185
salt shale and shells	1355
lime and shale	1460
lime shells & shale	1590
shale and shells	1704
lime	1825
lime and shale	1935
lime shells and shale	2040
shale and shells	2140
shale and lime	2250
shale	2465
lime and shale	2628
lime	2750
shale and lime	2795
lime	2875
shale and lime	2970
lime	3250
broken shale	3259
lime	3270
lime and chert	3287
shale and chert	3310
shale and lime	3332

Total Depth.

Conglomerate 3262 $\frac{1}{2}$ - 3332

Top Oswald 2981