


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - H.V. **ELWELL**  
Farm - Janssen No. 2

SEC. 29 T. 17 R. 10W  
CS  $\frac{1}{2}$  NW SW

Total Depth. 3254  
Comm. 3-25-46 Comp. 4-4-46  
Shot or Treated. Acidized 500' - 1000 Gal.  
Contractor. Ferrell-Young Drlg. Co.  
Issued. 8-24-46

County. Ellsworth  
KANSAS



CASING:  
10" 205' Cem.  
7" 3247' "

Elevation. \_\_\_\_\_

Production. Pot. 596 Bbls.

Figures Indicate Bottom of Formations.

Cellar	4
shale & shells	1155
shale, shells&lime	1350
lime & shale	1485
lime	1665
lime & shale	1885
lime	2000
lime brkn	2115
shale	2130
shale & shells	2280
lime & shale	2570
lime	2830
shale, lime, shells	2945
shale	2960
lime & shale	3010
lime	3254
Total Depth	

Tops: R.T.M

Lansing	2959
Detrital Zone	3235
Arbuckle	3240

5" 3247' Cem.

Drilled Cem. & shoe @ 3245.  
Clermed oil and hole made smell  
show free oil.

3245-3247.5 (SIM) Dense fine  
grained Dolomite. Trace spotted  
stain. NoProsity. No free oil.

3247.15 3248.5 Dolomite same plus  
some green shale.

3248.5 3253.5 Cable tool T.D.  
3253.5. Dense coarse grained to  
sucrose dolomite with pin point  
prosity.

Hole filled 450 to 500' oil in 2hrs.  
Filled 6258 oil in 3 hr. To  
Acidized.