

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

Company H.V. ELWELL
Farm Janssen No. 5

SEC. 29 T. 17 R. 10W
NW₆ SW

Total Depth. 3270
Comm. 5-6-46 Comp. 5-19-46
Shot or Treated. Acidized 500 Gal.
Contractor. Ferrell-Young Drlg. Co.
Issued. 8-31-46

County. Ellsworth
KANSAS



CASING:
10 3/4" 227' Com.
7" 3263' Com.

Elevation. _____

Production. Pot. 761 Bbls.

Figures Indicate Bottom of Formations.

cellar	4
shale & shells	1275
lime & shale	1570
lime & sand	1705
lime & shale	1840
lime	1935
lime & shale	2710
lime	2770
lime & shale	2960
lime	3165
lime & shale	3210
lime	3270
Total Depth	

Cable tool completion:
Completion data corrected
to derrick floor.

3261 7" casing.

3261-3262 Med. grained crystalline
dolomite with fresh wht chert;
some porosity; hole made 1 1/2 B
of free oil.

3262-3266 Material same to slighty
more dense. (less porosity)

3266-3270 TD Coarse grained crystalline
dolomite with good porosity & saturation.
(Fill up & record not available for
this report.

Tops: RTM

Lansing wht	2959
Conglomerate(cherty)	3241
Arbuckle	3262
Rotary TD	3267