

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - H. V. ELWELL
Farm Janssen No. 7

SEC. 29 T. 17 R. 10 W
SW NE SW

Total Depth. 3294'
Comm. 6-16-46 Comp. 6-27-46
Shot or Treated. No Acid.
Contractor. Ferrell-Young Drlg. Co.
Issued. 9-14-46

County. Ellsworth
KANSAS



CASING:
10 3/4" 206' Cem.
7" 3284' Cem.

Elevation. _____

Production. Pot. 291 B.

Figures Indicate Bottom of Formations.

shale & shells	60
sand & shells	90
shale & shells	200
shale	450
shale & shells	575
lime sdy	590
shale & shells	815
shale	845
anhydrite	870
shale & shells	1335
lime brkn	1390
shale & lime	1625
lime sdy	1675
sand, sdy lime	1750
lime & shale	2630
lime	2650
lime & shale	2720
lime	2895
lime & shale	2965
lime	3000
lime & shale	3045
lime	3248
conglomerate	3285
Arbuckle	3294
Total Depth.	

Tops:

Anhydrite	845
Lansing	2968
Conglomerate	3248
Arbuckle	3285

Cable Tool Completion

- 3284-88' Cement & shoe; rotary
cavings & traces of
dolomite.
- 3288-90' Dense to coarse xlyn
dolomite; poor por. &
poor stain; traces of
sand; some green shale
no free oil.
- 3290-92' Med. grained sli. weather-
ed dolomite w/sand inclusions
having some poor staining;
pale green shale.
- 3292-94' Fresh med. grained xlyn
dolomite w/good por. & good
stain. Hole filled 2000' oil
in 12 hrs.