

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - H. V. ELWELL
Farm - Janssen No. 8

SEC. 29 T. 17 R. 10 W
SW SE SW

Total Depth. 3265'
Comm. 6-29-46 Comp. 7-11-46
Shot or Treated. None.
Contractor. Ferrell-Young Drlg. Co.
Issued. 9-21-46

County. Ellsworth
KANSAS



CASING:
10 3/4" 218' Cem.
7" 3241' Cem.

Elevation. _____

Production. Pot. 1412 B.

Figures Indicate Bottom of Formations.

cellar	4
rock & clay soil	70
shale & shells	218
shale, shells, & red bed	470
shale & shells	560
lime sdy	585
shale & shells	1295
anhydrite	1385
lime & shale	1485
lime brkn	1700
shale & shells	1775
shale & lime	1965
lime	2065
shale & lime	2615
lime	2895
shale & lime	2950
lime	3229
conglomerate	3239
Arbuckle	3265
Total Depth.	

Tops:
Anhydrite 1295
Lansing (Wh) 2968
Conglomerate (cherty) 3229
Arbuckle 3239

- 3236-38' Cement & shoe; some fine grained to sucrose dolomite w/poor por. & lgt stain; no free oil.
- 3238-41' Dense fine grained cherty dolomite w/fair spotted stain & poor por.
- 3241-46' Dense gy to wh fine grained dolomite; no stain poor por.
- 3246-51' Same.
- 3251-53' Inc. in por., in med coarsely xlyn dolomite w/lgt stain.
- 3253-57' Dolomite same; less por.; lgt stain.
- 3257-61' Fine to med. grained dolomite good por. & staining; some rounded free quartz; Free oil.
- 3261-65' Material same; good por. Hole filled 2000' oil in 3 hrs.