


**WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY**  
 508 East Murdock, Wichita, Kansas

Company- STANOLIND OIL & GAS COMPANY  
 Farm- M. stumps "B" No. 3

SEC. 30 T. 17 R. 10W  
 SW NE NE  
 990' S of NL, 990' W of EL, NE  $\frac{1}{4}$

Total Depth. 3292 PB 3015  
 Comm. 2-21-53 Comp. 3-4-53  
 Shot or Treated.  
 Contractor.  
 Issued. 3-2-53

County Ellsworth  
 KANSAS



**CASING:**  
 8 5/8" 577' cem w/350 sx  
 6" 3282' cem w/ 75 sx

Elevation. 1812 RDB

Production. 77 Bbls & no water

Figures Indicate Bottom of Formations.

clay	50
clay, shells	90
sand	105
red rock	250
red rock, shale	300
shale, shells	340
clay, sand	530
red bed	570
anhydrite	600
shale, shells	1680
shale, lime	2705
lime	2830
lime, shale	2955
lime, shale	2970
lime	3243
lime, shale	3251
conglomerate	3277
dolomite shaley	3282
dolomite	3286 RTD
dolomite	3292
Total Depth PB 3015	

Tops:  
 Lansing- Oil Bearing 2955  
 Arbuckle-Oil Shows 3277

Total Depth  
 By Rotary Drill 3286  
 By Schlumberger 3284  
 Cable tools drlg 3286-3292  
 T.D. of well 3292  
 plugged back depth 3015  
 producing from perf. 2988-2993  
 well completed 3-31-53  
 as a Lansing producer  
 Lansing 2955-3277