


GULF OIL CORP.
Mary M. Grizzell No. 5.

SEC. 31 T. 17 R. 10W
NW 1/4 NW

Total Depth. 3287'
Comm. 4-26-37 Comp. 5-26-37
Shot or Treated. 2000 & 4000 Gals.
Contractor.
Issued. 9-18-37

County. Ellsworth



Elevation.

CASING:
10 3/4" 214'
6 3271'

Production. Pot. 1240 B.
No wtr.

Figures Indicate Bottom of Formations.

surface clay	15
sand, shale & shells	203
shale & shells	275
shale & shells-red	
bed	591
shale & shells	1063
salt	1262
shale & shells	1363
shale & brkn lime	1445
shale & shells	1458
shale hrd & lime	1498
shale & shells	1598
sdv shale & lime-	
shell	1748
shale & lime-shells	1765
lime & shale	1819
brkn lime & shale	1896
sdv shale & lime	
shells	1996
shale & shells	2195
sdv shale	2322
sdv shale & shells	2393
brkn lime & shale	2555
brkn lime	2655
sand & sdv lime	2664
lime	2856
shale & lime	2934
shale & lime-brkn	3024
lime	3058
brkn lime	3079
lime sft	3082
shale & lime	3094
lime sft	3112
lime	3122
lime hrd	3168
lime	3178
brkn sand	3190
lime	3230
shale	3240
shale & shells	3244
lime	3257
shale	3264
shale hrd	3287
shale brkn	3274
lime brkn	3285
lime	3287
Total Depth.	

Siliceous lime 3270-87