


SKELLY OIL CO.
W.T.Smith No. 3.

SEC.32 T.17 R. 10 W
CN $\frac{1}{2}$ SE NW
330'f NL 660'f EL S $\frac{1}{2}$ NW $\frac{1}{4}$

County. Ellsworth

Total Depth. 3250'
Comm. 10-11-41 Comp. 11-14-41
Shot or Treated.
Contractor. J.I.Roberts Drlg.Co.
Issued. 2-7-42

RotaryO-3247
Cable 3247-50



CASING:
8 5/8" 213' Cem.
4 1/2" 3246' SIM Cem.

Elevation.

Production. Pot.610 B.

Figures Indicate Bottom of Formations.

surface sand & clay	120
sand & shale	217
shale & strks iron	571
red bed & strks lime	808
lime & shale	901
lime, shale, salt	1270
anhydrite	1365
lime & shale	1720
lime	1835
lime & shale	2781
lime	2822
lime & shale	3238
chert gy & shale	3243
chert gy, trace sand & shale	3248
dolomite finely cryst, slight porosity & stained	3250
dolomite coarsely gy cryst, slight porosity & stained	3251
Corr. 3251 SIM rotary table equals 3247 SIM DF	
dolomite gy & brown coarsely cryst, fair porosity & sat. -	
1000' OIH in 2hrs	3250
Total Depth.	

Before acid 1000' OIH 2 H.
After acid POB 8 hrs
203.31 BO, no wtr to
estb. Pot. of 610 B.

11-14-41 500 Gals.3246-50
11-15-41 1000 Gals.3246-50

Tops: Lansing lime 2946
Arbuckle lime 3244
SIM

Pay formation 3246-50