


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

TRANSWESTERN OIL CO.
Dougherty No. 1

SEC. 32 T. 17 R. 10W
SEc NE

Total Depth. 3275.
Comm. 9-22-38 Comp. 10-12-38
Shot or Treated - No acid.
Contractor. Iron Drlg. Co.
Issued. 11-19-38

County Ellsworth.



CASING.

10" 266' 7" 3260'

Elevation.

Production. Pot. 1102 B.

Figures Indicate Bottom of Formations.

surface	243
shale and red bed	355
shells and red bed	530
anhydrite	567
shells & red bed	655
shale and shells	995
salt	1175
shale and shells	1302
lime and shale	1411
lime	1500
shale and lime	1610
sand	1638
lime	1694
lime and shale	2060
lime	2127
shale and lime	2354
shale and shells	2429
lime and shale	2740
lime	2800
lime and chert	2813
lime	2825
broken lime and shale	2890
lime and shale	2950
lime	2980
lime and shale	3160
lime	3212
lime & conglomerate	3250
lime and chert	3263
dolomite light	3265
dolomite and green shale	3267
dolomite buff	3268
Ulitic dolomite	3270
dolomite light	3275
Total Depth.	