

17950J
Smith and Ash #1 Stratman,
NW NE NE, 12-17S-10W.
Elevation 1800'.

Pennsylvanian conglomerate. 3241-3250'

3241-3250 Lime, pink and white. Sand, medium to coarse, with about
5% chert.

Ordovician Top 3250' Sub-sea, minus 1450'

Simpson 3250-3263'

3250-3257 Shale, green, sandy.

3257-3263 Sand, fine, cemented; with shaly streaks. Oil show.

3259-3263' Liner run to 3261' after drilling to 3266'

Arbuckle 3263-3284' Penetration 21'. Sub-sea, minus 1463'

3263-3270 Miller, zone 9. Swabbed 33 bbls. per hr. at 3266'.

3270-3280 Miller, zone 10. Swabbed 45 bbls. per hr. at 3276'.

3280-3284 Purcell, zone 3. Swabbed 75 bbls. per hr. at 3284'.

Correlated with Alyward #2 and #3 Stratman, both in 1-17S-10W.