

527500

Alyward #3 Stratman,  
SE SW SE, 1-17S-10W.  
Elevation 1804'

Note: Samples carried a SIE correction 3280 equals 3290'. The log was corrected on this basis, so all points are 10' than carried in Price's letter #16, 1932.

Pennsylvanian conglomerate. 3238-3266'

- 3238-3247 Variegated clay shales.
- 3247-3255 Sandy gray lime and variegated shales.
- 3255-3260 Sand, with rare chert. Variegated shale.

Ordovician Top 3260' Sub-sea, minus 1466'

Simpson 3260-3266' Cemented sand, fine. Loose sand, coarse.

Arbuckle 3266-3400' Penetration 34' Sub-sea, minus 1462'

- 3266-3276 Miller, zone 9 Small oil show, 3270' Limer at 3270'.
- 3276-3286 Miller, zone 10 ~~XXXXXXXXXXXXXXXX~~ 3277-3286, oil rose  
1300' in 4 hrs. ~~XXXXXXXXXXXXXXXXXXXX~~
- 3286-3293 Purcell, zone 3 Swabbed 10 bbls. per hr. at 3293'
- 3293-3295 Purcell, zone 4
- 3295-3298 Purcell, zone 5
- 3298-3300 Purcell, zone 6 Small amount of water at 3300'.

Correlated with Prairie #1 Stratman, 1-17S-10W.